

Purchasing Department
P.O. Box 13145 • Roanoke, VA 24031
PHONE (540) 853-1348
FAX (540) 853-2836

March 31, 2023

## IFB 3103 JOHN P. FISHWICK MIDDLE SCHOOL ROOF REPLACEMENT

Addendum #1

This addendum provides answers to questions received from contractors as of March 28, 2023, minor clarifications based on discussions during the Prebid meeting, as well as a copy of the Asbestos Survey.

### **Questions & Answers:**

#### **Q1-** Per the spec section below:

- F. Attached Insulation: Install each layer of insulation and secure to deck using adhesive or fasteners specifically designed and sized for fastening specified board-type roof insulation to deck type indicated. Use foam adhesive over any areas of concrete roof deck. Screw fasteners may be used elsewhere where rooms below have lay-in ceilings.
  - 1. Fasten insulation according to the insulation and roofing system manufacturers' written instructions to meet specified wind-uplift requirements.

Are fasteners only to be used in areas where lay-in ceilings are?

A1 – The intention for roof areas K & N is for the roofing system layers to be attached using adhesives and not mechanically fastened to the deck. Mechanical fastening of base insulation to the tectum deck of roof area K is at the contractor's option and methods will be reviewed and approved during the submittal process. Fasteners are acceptable where required by the manufacturer to achieve the design wind uplift resistance particularly in the overlay areas where adhesive attachment of new insulation to existing roofing system is not feasible. Overlay areas generally occur where there are ceilings.

- **Q2 -** A-102 Detail #2 and #4 show horizontal termination. This is not acceptable for a 30yr warranty by the manufacturer, additional detail information is required.
- **A2 –** For the Base Bid TPO-30, details #2 & #4 should be revised to include an edge metal termination such as "Carlisle Secure edge" or similar on the outside of the precast stone coping as necessary to achieve a 30-year warranty.
- Q3 Additional information is required for the existing skylight framing. They are only replacing the glazing (polycarbonate) infill but there's a lot of required performance info that is contingent upon what the existing skylight framing but it does not tell me what the existing framing system is, let alone what performance that existing skylight system is designed.
- A3 We have no additional information regarding the existing skylight construction. A structural engineer reviewed the existing conditions and developed specification section 05310 Steel Decking for add alternate #2 using the existing structure. Contractors should assume the existing skylight and structure meet the performance requirements detailed in specification section 08450 and bid replacement under add alternate #1 accordingly. Please review specification section 08450-5 paragraph 2.3 A, B, & C carefully. Any deficiency in the existing construction that precludes conformance with the specification requirements will be handled after award by change order.
- Q4 In the construction documents for Fishwick, in Section 02070 Selective Demolition paragraph 1.4B Asbestos, it says:
   "Areas of known asbestos-containing materials are shown in the Asbestos survey."
   I can't find that survey in the documents online or otherwise, could you direct me as to where I can find it.
- **A4 –** The asbestos survey was not included with the solicitation. It is attached to this addendum. There is no known asbestos in the roofing system.

### **CLARIFICATIONS:**

- 1. Roof Area K is over a gymnasium and part of roof area G is over a stage (Where the RTUs are located). Neither of these areas has a ceiling. The contractor will be responsible for protection of the floor and interior and any clean up resulting from roof tear off and installation.
- 2. Contractors should include in base bids all costs necessary for raising the RTUs on the plan North side of roof area G to achieve minimum flashing heights.
- 3. Reference specification section 07535-4 2.1 Manufacturers Acknowledging that Firestone Building Products Company is now Holcim. The Elevate line of roofing materials is approved for use on this project.
- 4. Reference specification section 01030-2 3.1 B TPO roof thickness for this bid alternate to match the base bid warranty/ thickness. Please provide pricing for both a 60 mil and 80 mil thickness installation.

### SCHNEIDER LABORATORIES

INCORPORATED

2512 W. Cary Street • Richmond, Virginia • 23220-5117 804-353-6778 • 800-785-LABS (5227) • (FAX) 804-359-1475

Excellence in Service and Technology

# AIHA/ELLAP 100527, NVLAP 101150-0, NYELAP/NELAC 11413, CAELAP 2078, NC 593, SC 93003 LABORATORY ANALYSIS REPORT

Asbestos Identification by EPA Method¹ 600/M4/82/020 Using SLI A6

**ACCOUNT #:** 850-09-161

TREMCO SERVICE CORPORATION

**ADDRESS:** 14306 LONG GATE RD

MIDLOTHIAN, VA 23112

PROJECT NAME: Stone Wall Jackson M

JOB LOCATION: Roanoke Va

**PROJECT NO.:** 

**CLIENT:** 

PO NO.: SampleType: BULK

Client	SLI Sample		
Sample	Sample/ Identification/	PLM Analysis Results	
No.	Layer ID Layer Name	Asbestos Fibers	Other Materials
RS-1	30076855 Roof Cafateria		
Layer 1:	Roofing Material Black, Rubbery/Fibrous	None Detected	20% CELLULOSE FIBER 15% MINERAL/GLASS WOOL 65% NON FIBROUS MATERIAL
FS-1	30076856 Flash Cafateria		
Layer 1:	Flashing Black/Tan, Rubbery/Soft	None Detected	5% CELLULOSE FIBER 95% NON FIBROUS MATERIAL
RS-2	30076857 Roof Admin Office		
Layer 1:	Roofing Material Black/Yellow, Rubbery/Soft	None Detected	15% MINERAL/GLASS WOOL 85% NON FIBROUS MATERIAL
FS-2	30076858 Flash Admin Office		
Layer 1:	Flashing Black/Beige, Rubbery/Soft	None Detected	5% CELLULOSE FIBER 95% NON FIBROUS MATERIAL
RS-3	30076859 Roof Elevator A		
Layer 1:	Roofing Material Black/Beige, Rubbery/Fibrous	None Detected	20% CELLULOSE FIBER 15% MINERAL/GLASS WOOL 65% NON FIBROUS MATERIAL

### **Total Number of Pages in Report: 4**

Results relate only to samples as received by the laboratory.

Visit www.slabinc.com for current certifications.

2/9/2009

2/23/2009

2/24/2009

2/24/2009

DATE COLLECTED:

**DATE RECEIVED:** 

**DATE ANALYZED:** 

DATE REPORTED:

Client	SLI	Sample			
Sample	Sample/	Identification/	PLM A	PLM Analysis Results	
No.	Layer ID	Layer Name	Asbestos Fibers	Oth	ner Materials
RS-4	30076860	Roof Boiler Room			
Layer 1:	Roofing Materia	al	None Detected	15%	CELLULOSE FIBER
	Black, Rubbery	/Fibrous			MINERAL/GLASS WOOL
				70%	NON FIBROUS MATERIAL
RS-5	30076861	Roof Canopy B			
Layer 1:	Roofing Material		None Detected	10%	CELLULOSE FIBER
	Black, Rubbery	/Fibrous			MINERAL/GLASS WOOL
				75%	NON FIBROUS MATERIAL
FS-5	30076862	Flash Canopy B			
Layer 1:	Flashing		None Detected	100%	NON FIBROUS MATERIAL
	Black, Rubbery				
RS-6	30076863	Roof Stairwell			
Layer 1:	Roofing Materia	al	None Detected	10%	CELLULOSE FIBER
,	Black, Rubbery			12%	MINERAL/GLASS WOOL
-				78%	NON FIBROUS MATERIAL
FS-6	30076864	Flash Stairwell			
Layer 1:	Flashing		None Detected		CELLULOSE FIBER
	Black/Yellow, P	lubbery/Soft		97%	NON FIBROUS MATERIAL
RS-7	30076865	Roof Front Canopy A			
Layer 1:	Roofing Materia	al	None Detected		CELLULOSE FIBER
	Black, Rubbery	/Fibrous			MINERAL/GLASS WOOL
				78%	NON FIBROUS MATERIAL
FS-7	30076866	Flash Front Canopy A			
Layer 1:	Flashing		None Detected	100%	NON FIBROUS MATERIAL
	Black, Rubbery				
RS-8	30076867	Roof Class Room B			
Layer 1:	Roofing Materia	al	None Detected	6%	CELLULOSE FIBER
	Black/White, R	ubbery/Granular		94%	NON FIBROUS MATERIAL
RS-8A	30076868	Roof Class Room B			
Layer 1:	Roofing Materia	al	None Detected	100%	NON FIBROUS MATERIAL
	Black, Rubbery				

### **Total Number of Pages in Report: 4**

Results relate only to samples as received by the laboratory.

Visit www.slabinc.com for current certifications.

Client	SLI Sample			
Sample No.	Sample/ Identification/ Layer ID Layer Name	PLM Ai Asbestos Fibers	nalysis Results Other Materials	
FS-8	30076869 Flash Class Room A	7,0000,001,100,00		
Layer 1:	Flashing Black, Rubbery	None Detected	100% NON FIBROUS MATERIAL	
RS-9	30076870 Roof Class Room A			
Layer 1:	Roofing Material Black/Yellow, Rubbery/Soft	None Detected	2% CELLULOSE FIBER 98% NON FIBROUS MATERIAL	
FS-9	30076871 Flash Class Room A			
Layer 1:	Flashing Black, Rubbery/Fibrous	None Detected	10% CELLULOSE FIBER 15% MINERAL/GLASS WOOL 75% NON FIBROUS MATERIAL	
RS-10	30076872 Roof Fitness			
Layer 1:	Roofing Material Black/Beige, Rubbery/Fibrous	None Detected	20% MINERAL/GLASS WOOL 80% NON FIBROUS MATERIAL	
FS-10	30076873 Flash Fitness			
Layer 1:	Flashing Black/Beige, Rubbery/Soft	None Detected	3% CELLULOSE FIBER 97% NON FIBROUS MATERIAL	
RS-11	30076874 Roof Loading			
Layer 1:	Roofing Material Black/Beige, Rubbery/Fibrous	None Detected	25% CELLULOSE FIBER 75% NON FIBROUS MATERIAL	
RS-11B	30076875 Roof Loading			
Layer 1:	Roofing Material Black, Rubbery	None Detected	100% NON FIBROUS MATERIAL	
FS-11	30076876 Flash Loading			
Layer 1:	Flashing Black/Beige, Rubbery/Soft	None Detected	12% CELLULOSE FIBER 88% NON FIBROUS MATERIAL	
RS-12	30076877 Roof Gym			
Layer 1:	Roofing Material Black/White, Rubbery/Granular	None Detected	4% CELLULOSE FIBER 96% NON FIBROUS MATERIAL	

### **Total Number of Pages in Report: 4**

Results relate only to samples as received by the laboratory.

Visit www.slabinc.com for current certifications.

Client	SLI Sample/	Sample Identification/		
Sample			PLM Analysis Results	
No.	Layer ID	Layer Name	Asbestos Fibers	Other Materials
RS-12B	30076878	Bottom Roof Gym		
Layer 1:	Roofing Mater Black, Bitumin		None Detected	3% CELLULOSE FIBER 97% NON FIBROUS MATERIAL
FS-12	30076879	Flash Gym		
Layer 1:	Flashing Black, Rubber	у	None Detected	100% NON FIBROUS MATERIAL

Analyst: HALA A. OSMAN

Reviewed By:

Hind Eldanaf, Team Leader

**Total Number of Pages in Report: 4** 

Results relate only to samples as received by the laboratory.

Visit www.slabinc.com for current certifications.